

  
**BILL / INVOICE**

(23)

(24)

**SCHEDULE OF WORK**

**of work:-** Replacing of Senior Computer lab switch boards and wiring.

Description of Item	Qty	Rate	Amount
Supplying and drawing of following sizes of FRLS PVC insulated copper conductor single core cable in the existing surface/recessed steel /PVC CONDUIT as required.			
a) 10X2.5 sq mm	60 mtr		
b) 8X2.5 sq mm	35 mtr		
c) 6X2.5 sq mm	25 mtr		
d) 4X2.5 sq mm	25 mtr		
e) 2X2.5 sqmm	75 mtr		
f) 1X2.5 sqmm in green color for earth	220 mtr		
2 Wiring for circuit/submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper single core cable in surface/recessed medium class PVC conduit as reqd			
a) 4X6 sqmm + 2X6sqmm	35 mtr		
a) 2X6 sqmm + 1X6sqmm	20 mtr		
3 Supplying and fixing of following size / Modules GI box and cover plate for modular switches in recess etc as required			
a) 8 module	28 nos		
b) 12 module	28 nos		
4 Supplying and fixing of switch/socket on the existing switch box/cover including connection as required.			
a) 5/6amp switch	168 nos		
b) 6pin 15/16 A socket outlet	168 nos		
5 supplying and fixing 20A 240 volts SPN industrial type socket outlet with 2 pole and earth, metal enclosed plug top along with 20A c curve SPMCB, in sheet steel enclosure, on surface or	4 nos		

BILL / INVOICE

(23)

21a

6	Suppluing and fixing following size of medium class PVC conduit along with accessories in surface/recees including painting in caseof surface conduit or cutting the wall and making good the same in case of recessed conduit as required				
	a)40 mm	60 mtr			
	b)32 mm	60 mtr			
			TOTAL		
	0				